



(12)

EUROPEAN PATENT SPECIFICATION

(45) Date of publication and mention
of the grant of the patent:

14.04.1999 Bulletin 1999/15

(21) Application number: 94929964.8

(22) Date of filing: 29.09.1994

(51) Int. Cl.⁶: B01L 11/00

(86) International application number:
PCT/US94/11090

(87) International publication number:
WO 95/10035 (13.04.1995 Gazette 1995/16)

(54) AUTOMATED STAINING APPARATUS AND METHOD

AUTOMATISCHES EINFÄRBUNGSVERFAHREN UND - VORRICHTUNG

PROCEDE ET APPAREIL AUTOMATIQUES DE COLORATION DES PLAQUETTES DE
MICROSCOPE

(84) Designated Contracting States:

AT BE CH DE DK ES FR GB GR IE IT LI LU MC NL
PT SE

(30) Priority: 29.09.1993 US 129243

(43) Date of publication of application:

24.07.1996 Bulletin 1996/30

(73) Proprietor:

BIOGENEX LABORATORIES
San Ramon California 94583 (US)

(72) Inventors:

- TSEUNG, Ken
Fremont, CA 94538 (US)
- WONG, Wai, Bun
Fremont, CA 94556 (US)
- JONES, Christopher, Michael
Walnut Creek, CA 94596 (US)

• KALRA, Krishan, L.

Danville, CA 94506 (US)

(74) Representative:

Baldock, Sharon Claire et al
BOULT WADE TENNANT,
27 Furnival Street
London EC4A 1PQ (GB)

(56) References cited:

- | | |
|-----------------|-----------------|
| EP-A- 0 255 057 | EP-A- 0 321 889 |
| WO-A-92/01919 | WO-A-93/03451 |
| DE-A- 3 805 808 | US-A- 4 030 341 |
| US-A- 4 042 999 | US-A- 4 224 277 |
| US-A- 4 305 722 | US-A- 4 308 822 |
| US-A- 5 009 185 | US-A- 5 225 325 |
| US-A- 5 231 029 | |
- FISHER SCIENTIFIC CATALOG, published 1988,
pages 168-169, see "Flame Spreaders" and
"Burner Wing Top for Glass Bending".

Description

[0001] Microscopic examination of unstained cell and tissue preparations often suffers from a lack of contrast between individual cells and the background matrix or between individual parts of cells. In order to alleviate this difficulty, dyes (stains) that are taken up differentially by cells or parts of cells have been used in microscopic examination of tissues for over a century.

[0002] Because of the manner in which slides with tissue preparations are prepared (see Elias, J., "Immunohistopathology: A practical Approach to Diagnosis" ASCO Press, 1990, pp. 3-4, for examples of such preparation), the size and/or location of a tissue sample on a microscope slide can vary considerably within a relatively large area of the slide. In order to apply a stain to the correct location on a slide and to provide rinsing and other manipulation steps at appropriate times and in right amounts, until recently all such staining operations were carried out by hand. It is apparent, however, that modern laboratories that examine large numbers of tissue preparations find it desirable to automate the staining process. Accordingly, a number of manufacturers have developed equipment for automated staining of tissue preparations on microscope slides.

[0003] For example, U.S. Patent No. 4,985,206 describes an apparatus and process for automating the application of staining reagents to a thin tissue section mounted on a microscope slide. The apparatus and method use a channel-defining element that is assembled with the microscope slide to provide an enclosure of capillary dimensions into which liquids can be injected. Liquids are added sequentially to the capillary space, where the addition of a new liquid forces out the previous liquid. A plurality of these assemblies of microscope slides and specialized covers can be placed in a rack on an apparatus for automated addition of liquids.

[0004] A further automated immuno staining apparatus referred to as the Ventana 320TM is produced by Ventana Medical Systems, Inc. of Tucson, Arizona. This apparatus applies a liquid known as Liquid CoverslipTM to each slide prior to reagent addition. Liquid Cover-slipTM is a non-aqueous material having a density less than that of water. When a reagent dissolved in water is added to a microscope slide, the reagent sinks to the bottom of the Liquid CoverslipTM for spreading across the surface of the slide. Slides are organized on a carousel which rotates beneath a dispensing head for application of reagents or wash fluids.

[0005] Leica produces an automated staining apparatus known as the Jung Histostainer IgTM. This is another carousel-type device, but reagents are applied by a spraying operation rather than by dropping liquid onto an organic film. The apparatus contains a permanent reagent spraying head that can be moved along a single axis to provide spray coverage over a microscope slide located on the rotating tray when the slide is rotated into a position underneath the head. Excess reagent is

removed by a permanent clearing nozzle which blows air in a pressure front across the slide, forcing excess liquid off at the completion of the reagent incubation step.

5 [0006] All of these apparatuses have attempted to solve certain conflicting goals in automated apparatuses of this type. For example, it is desirable to use a minimum of expensive or toxic reagents, particularly reagents used in immuno staining (e.g., antibodies and other reagents of biological origin), while insuring that complete coverage of the microscope slide by the reagent will occur. However, the last-referenced spraying operation above uses an excess of reagent which must be removed in order to obtain satisfactory coverage. 10 The other techniques require additional manipulative steps, such as the use of a hand-assembled cover or an additional liquid reagent to provide for proper spreading of the reagent. It would be desirable to have an automated apparatus that can use regular microscope slides without additional manipulation and that does not require the use of either excess reagent or the use of an organic liquid with additional manipulation and disposal steps. Accordingly, further developments that allow individual slides to be treated differently in a single batch 15 operation and that provide an automated procedure that uses reagents efficiently remain needed.

20 [0007] These objects have been attained by providing an automated staining apparatus, generally comprising a supporting framework; an arm moveable in three dimensions attached to the framework; means for moving the arm; a hollow tip head located on the arm; means for alternatively supplying positive or negative gas pressure to the hollow tip head; a removable wash/blow tip having an exit slit substantially equal in length to the width of a microscope slide, the wash/blow tip being adapted to be removably attached to the hollow tip head by a preselected movement of the arm; a wash/blow tip holder at a first fixed location on the framework; a reagent application tip holder at a second fixed location on the framework for holding a reagent application tip, the reagent application tip being adapted to be removably attached to the hollow tip head by a preselected movement of the arm; a reagent container holder at a third fixed location on the framework; a microscope slide holder at a fourth fixed location on the framework, the microscope slide holder being adapted to removably contain the microscope slide; and control means for controlling movement of the arm between the locations, whereby the tip head picks up the wash/blow tip or the reagent application tip in response to movement of the arm under control of the control means and moves to one or more of the locations to pick up a reagent in the reagent container or dispense the reagent on the slide or to dispense a gas or liquid through the wash/blow tip over the slide.

25 [0008] The invention also provides various subcomponents of the apparatus that are specifically adapted to the staining of tissue on slides with this apparatus. A key

component is a wash/blow head which comprises a hollow body member formed at least two detachable parts having an internal cavity which is accessible when said parts are detached; a linear exit slit providing fluid communication between the internal cavity and the external environment surrounding the tip, the linear exit slit being substantially identical in length to the width of a microscope slide with which the tip is to be used; and means for removably attaching the hollow body member to a hollow tip head in the apparatus of the invention and providing access to the internal cavity for gas or liquid supplied through the tip head.

[0009] In addition, the apparatus carries out a technique for applying stain to tissue preparations on unknown (to an instrument) locations on individual slides that is not specific to the apparatus of the invention but which can be adapted to other automated equipment or to hand operations. This method comprises applying a thin film of water to a horizontal upper surface of a microscope slide and applying a water soluble staining reagent to the film of water in a pattern insufficient to fully cover the slide when the slide is dry, whereby the reagent diffuses through the film to reach substantially all of the surface on which a tissue may reside while using only a minimum volume of reagent.

[0010] The apparatus will now be described along with its operation, after which the apparatus and various component parts will be described in detail with reference to the figures that form part of this specification.

[0011] The apparatus of the invention comprises a supporting framework to which an arm movable in three dimensions is attached. Motors or other means for moving the arm are provided under the control of a computer or other electronic control device that allows programming of movement of the arm between various work locations on or within the framework. A hollow tip head is located on the arm so that liquids or air can be dispensed or withdrawn through the tip head to provide for the various work operations described below. In preferred embodiments of the invention a single, hollow tip head is provided to which individual tips having different functions will be attached. In a most preferred embodiment, the tip head is adapted to pick up disposable plastic pipette tips from the standard containers in which such tips are supplied (for example, Catalog No. 3510-R from E&K Scientific Products, Saratoga, California). These disposable pipet tips are currently sold in a container which presents the base of the tip for insertion of a hand-held pipette by a pressing motion of the end of the pipette body into the hollow tip, the tips being arranged in an array so that all individual tips in the container are accessible to the operator. As will be apparent from the description below, the same standard box of pipet tips can be used in the apparatus of the present invention.

[0012] A key element of the apparatus of the invention is a removable wash/blow tip having an exit slit that is usually equal or substantially equal in length to the

width of a microscope slide. If the slit is not equal to the width of a microscope slide with which it is intended to be used, it is preferred that the slit be slightly wider than the microscope slide. A narrower slit is less efficient in removing liquid from the microscope slide surface as described below. However, the practical width of a slit is limited by the desire to have a number of microscope slides closely arranged together in the apparatus of the invention and further to avoid wasting buffer or other wash solutions that are applied to a slide through the tip. In the blowing operation that removes excess wash/buffer solution, the exit slit on the wash/blow tip provides a "wall" of air that pushes excess liquid from the surface of a microscope slide as the tip is passed over and parallel to a microscope slide (described later in detail). This wash/blow tip is adapted to be removably attached to the same hollow tip head to which the disposable pipet tips are attached. Both of these attachment (and optionally detachment) operations can be carried out by a preselected movement of the arm, much in a same manner that disposable pipet tips are now pressed onto and later removed from the end of a hand-operated pipet.

[0013] The framework of the apparatus is provided with holders at fixed locations on the framework for both the wash/blow tip and the reagent tips, among other removable items. Thus, programming of the arm to move to a particular fixed location and carry out a preselected motion or other operation discussed herein allows the individual tips to be placed onto or released from the hollow tip head. A holder for a reagent container (the reagent container being for stain or various solutions associated with staining) and a microscope slide holder are also present on a framework at other fixed locations. Thus, standardized motions of the arm can be programmed into the control unit so that individual microscope slides at specific fixed locations in the microscope slide holder can be treated with reagents and/or wash fluids obtained from reagent containers or from liquids supplied through the hollow tip head on the movable arm.

[0014] In a typical operation of the apparatus of the invention, multiple slides, each generally having a tissue sample at some location on its upper surface, are placed horizontally in a tray that is inserted into the apparatus at a fixed location, usually at a location having registration pins that fit into registration holes in the tray (or similar registration means) so that the individual microscope slides are always located in the same relative positions on the frame of the apparatus. The apparatus is programmed as appropriate for the individual slides being treated and reagents, and reagent containers are placed at their own predetermined locations in the apparatus in the same manner as the tray described above. Likewise, reagent application tips are also made available for pickup by the moveable arm. For example, a standard box of 1-ml pipet tips can be placed at its pre-designated location in the apparatus.

[0015] Once all components are in place, the apparatus carries out all reagent application, incubation, heating (if necessary or appropriate) and sample rinsing steps to perform the desired staining operation. In a typical operating sequence, the movable arm picks up a detachable wash/blow tip having a slit exit, and a buffer solution is applied to each of the sample slides being treated in a particular cycle by a liquid supply line and wash buffer reservoir attached via the supply line to the hollow tip head. The apparatus then uses the same wash/blow tip to blow excess buffer off the slide prior to reagent delivery. This is accomplished by blowing air through the tip while the head travels down the length of the slide; a "wall" of air exits the slit and removes excess buffer from the slide without disrupting the tissue sample. A small amount of buffer is left on the slide to assist in reagent spreading. The wash/blow tip is then returned to its holder by the automated arm.

[0016] The arm then picks up a disposable pipet tip from the pipet tip box that has been inserted into the reagent application tip holder in the apparatus. The arm with the pipet tip attached picks up a reagent to be applied to a slide or to a group of slides from a reagent vial. A number of slides can be treated with reagent at the same time. The reagent is dispensed on the slide in a pre-assigned pattern that works in combination with the thin liquid film on the microscope slide to assure spreading of the reagent over the entire surface of the slide to which the tissue may be attached. The thin liquid film allows less reagent to be used than would be required if the film were not present to assist reagent spreading.

[0017] The disposable pipet tip is then discarded, and the movable arm picks up the wash/blow tip for adding buffer to and then blowing excess buffer off the next group of slides to be processed while the first group of slides are being incubated with the reagent, after which the wash/blow tip is returned to its holder. The arm then picks up the next available disposable tip from the tip box, and reagent is drawn into the tip and applied as before. Appropriate steps are repeated until all slides have been treated with reagent or until a reagent incubation is complete so that reagents must be removed from appropriate slides.

[0018] Once a reagent incubation is complete, slides are rinsed when the movable arm picks up the wash/blow tip again and buffer is applied to the slide to rinse off the majority of the reagent. The wash/blow head then blows the excess buffer from the slide, and the slide is rinsed a second time with the on-line buffer, if necessary. This procedure of rinsing and drying a slide is repeated as necessary depending upon the individual stain and the appropriate procedure for rinsing the reagent. The control mechanism, generally a programmable computer, keeps track of the time of the various incubation and repeats the steps above as appropriate in order to apply reagent to all of the slides that have been inserted into the tray.

5 [0019] A special feature of the apparatus of the invention that allows efficient use of reagents is the method of spreading reagents described above and further described in detail below. When a standard aqueous staining reagent is dropped onto a glass slide, the reagent tends to stay in the location where dropped rather than spreading over the entire surface area of the slide. Since the location of the tissue preparation on a slide is variable and may not be located in the same place from one slide to the next, automated procedures previously had to apply the reagent over the entire area of the slide. While this could be accomplished by applying a relatively large amount of a dilute reagent, not all staining operations allow the use of dilute reagents, and some stains are sufficiently expensive so that applying concentrated reagent over the entire slide, including areas where no tissue is present, would be a major cost of operation. Accordingly, a special application system has been devised for use in the apparatus of the present invention; this system can be used generally in the manner described here for other automated equipment.

10

15

20

[0020] The slide to which stain will be added is first washed with an aqueous wash solution, usually a buffer, that contains one or more surfactants which reduce the surface tension of water. However, it is not satisfactory merely to flood a slide with an aqueous solution of surfactant, since a concentrated reagent added to the slide will merely be diluted on the slide. Accordingly, the wash/blow tip of the invention is designed so that excess buffer can be blown off the washed slides to produce a thin film of the aqueous solution. The height of the wash/blow tip slit exit above the microscope slide, the pressure of the compressed air being blown through the tip, and the rate of movement of the tip are selected to leave a controlled amount of buffer on the slide. If too much buffer is left, the reagents will be diluted as discussed above and will not work correctly. If too little buffer is left, the buffer will evaporate prior to reagent application, and the reagents will not spread. Specific techniques for controlling the wash/blow tip to select the amount of buffer are described below.

25

30

35

40

[0021] In addition to the buffer and use of the wash/blow tip as described above, the method of the invention also provides dispensing of reagents on the slide in a pattern that assists spreading. A pattern is selected so that reagent is not required to diffuse for great distances through the surface film; for example, convoluted application pattern can be selected so that reagent need not diffuse more than one-fourth (or some other fraction) of the width of the microscope slide. The combination of the buffer film and the application pattern (usually dropwise or in a stream) ensures adequate coverage of the slide regardless of the location of the tissue and allows less reagent to be used than would be required in the absence of a surface film. In a typical operation, the amount of reagent added is less than that which would be required to cover the slide if no aqueous film were present on the slide.

45

50

55

[0022] In addition to these general operations and components of the invention, the apparatus of the invention can contain additional subsystems for convenience, such as drain pans, heating blocks, and other components that are described below in more detail.

[0023] The invention now being generally described, the same will be described in reference to the figures using the same reference numbers throughout to represent either identical parts that appear in different views of the same embodiment or parts in different embodiments that have identical functions.

[0024] Figure 1 shows a first embodiment of the invention in a plan view from above. In order to make visible the movable arm and other working parts of the apparatus, Figure 1 is illustrated without the normal cover that would normally form the upper surface of the apparatus and act, with remaining walls to enclose the working parts and microscope slides. In this view, the front of apparatus 10 is at the bottom of the figure.

[0025] In this view, movable arm 30 is visible in the upper-left (back-left when viewed horizontally) corner of the interior of framework 20. Framework 20 is formed from various components such as baseplate 22 and side plate 24 that form a cabinet surrounding the working parts of apparatus 10. The various locations (and the corresponding parts of the apparatus or materials that are inserted into the apparatus at these locations) are visible on base plate 22. Movable arm 30 will carry out the operations of the apparatus is visible in its home position in the back-left corner of the apparatus (upper-left portion of the Figure 1). Slightly in front of and to the right of the arm home position is a drain bin 26, which is simply a container into which pipet tips 90 (described later) are discarded. Drain bin 26 can be provided with a drain line to a waste container and in any event is removable from its standard location for disposal of tips (and optional draining of collected fluid). This and other parts of the apparatus are adapted to be retained in a specific location on baseplate 22 by providing matching projections and depressions or other means for locating the indicated part of the apparatus on the base plate at a fixed location.

[0026] Immediately in front of drain bin 26 in this first embodiment is the fixed location of a reagent application tip holder 100 (not visible in this view). In this first embodiment holder 100 is adapted to retain in position a standard pipet tip box 92 containing an array of disposable pipet tips 90. An example of an appropriate holder 100 for pipet tips 90 (actually for tip box 92) is a raised area on baseplate 22 around which the base of pipet box 92 snugly fits.

[0027] To the right of pipet tip box 92 is a reagent container holder 120, in this embodiment in the form of a reagent rack. The reagent rack 120 can either be affixed to the baseplate 22, or in the manner described above it can be adapted to be removable from the baseplate for loading with reagent containers 110 in a more convenient location. The reagent rack is adapted be to retained

by the baseplate in a fixed location and orientation, so that any given reagent container will always be in the same relative position on baseplate 22.

[0028] Immediately behind reagent rack 120 is wash/blow tip 70 and its holder 80. Below holder 80 is a drip pan 28, which can be connected to an external drain or merely made removable for disposal of wash liquids that may drip off of tip 70 when it is present in its holder 80.

[0029] To the right of wash/blow tip holder 80 and reagent rack 120 are four 10-well microscope slide trays 140. Each tray 140 is retained in a fixed location and orientation relative to baseplate 22 and the remainder of the frame so that each microscope slide retained in a well is in a fixed location relative to the baseplate 22. Visible through the open bottom surfaces of the wells of trays 140 are heating blocks 200 and drain pan 210; these components are described in more detail in later figures.

[0030] Movable arm 30 is moved to different locations over baseplate 22 by the action of various motors that operate in combination with sliding tracks to precisely position arm 30 at its desired location within Frame 20 in order to carry out the operations that are described here. Visible in Figure 1 at the top of the figure is the X-axis track 32, in this embodiment the X-axis being the principal longer horizontal axis of the apparatus. In the embodiment shown a single X-axis track 32 is supported at both ends on bearing shafts and brackets 34a (the left bracket) and 34b (the right bracket and shaft).

The Y-axis is the principle shorter horizontal axis of the embodiment as shown. A step motor is used in these embodiments under the control of the computer or other control apparatus (described later). Part of one motor mount 33' for X-axis motor 33 is visible in this figure. Bearing shafts 34' and shaft supports 34' are also visible as part of the Y-axis track. The Z-axis in this embodiment is the orthogonal vertical axis and is perpendicular to the plane of Figure 1.

[0031] In a preferred working embodiment, flexible electronic leads and tubing (both air and liquid supply lines) would be visible in this figure leading from movable arm 30 to appropriate fluid reservoirs or electronic control equipment. These lines are not shown in Figure 1 for the sake of clarity but are described later with respect to specific parts of the apparatus. These supply lines are sufficiently long and flexible so as to allow ready access of movable arm 30 to any location within the operating space required to carry out the operations of the apparatus. The various supply lines are usually retained in the upper portion of the interior framework 20, typically by use of an elastic supporting yoke that is attached to the supply lines and to various locations on the framework 20.

[0032] The same embodiment 10 of Figure 1 is shown in Figure 2. In this front view of the first embodiment of the invention, the movable arm 30 is shown in four different locations (i.e., Figure 2 does not show four sepa-

rate movable arms but merely four locations for a single arm). The left-most position of arm 30 is simply the home position to which the arm returns when not being used, which is selected for minimum interference with other operations, such as the insertion of microscope slides or disposable pipet tips into the cabinet-like interior of framework 20. The second position of arm 30 shown in Figure 2 is at the location for pickup of removable wash/blow tip 70, which is retained in its wash/blow tip holder 80 at a fixed location on framework 20. The double-headed arrow on Z-track 36 indicates that movable arm 30 is moved downward at this location so that hollow tip head 40 is inserted into the stem of wash/blow head 70. Wash/blow tip holder 80 is adopted to surround and retain wash/blow tip 70 so that an upward motion of the arm while the tip is in its normal resting position will remove tip head 40 from tip 70. However, the front of wash/blow tip holder 80 is open so that a forward motion of arm 30 releases tip 70 from holder 80.

[0033] After wash/blow tip 70 is moved forward and released from its holder 80, movable arm 30 is moved upward so that tip 70 is above any interfering part of the apparatus, and wash/blow tip 70 is moved to an appropriate location while the tip is in the raised position as shown by the third position of the movable arm with a double-headed horizontal arrow on Z-track 36. When the movable arm reaches the appropriate location above a pre-selected microscope slide, as shown in the fourth position of the movable arm 30, the arm is again lowered to position the wash/blow tip at an appropriate height above the selected microscope slide. In a preferred embodiment, tip 70 is positioned at one end (e.g., the front end) of microscope slide 130 and a buffer or wash liquid supplied through liquid supply line 62 (not visible in this figure; see Figure 12) as tip 70 is moved in a single pass to the rear of microscope slide 130. If desired, the blow-dry operation can then be carried out on the same slide by supplying pressurized air through an air supply line as tip 70 is moved back to the front position of microscope slide 130. However, it is also possible and preferred in some embodiments to move tip 70 to a second microscope slide for addition of buffer so that buffer added to the first microscope slide can remain on the slide for a pre-selected period of time prior to removal. After buffer has been added to a pre-selected number of slides, movable arm 30 is returned to the first slide of the group, and the blow operation can commence.

[0034] After completion of a wash cycle in the manner described, movable arm 30 is returned to the pickup position shown in the second location of the movable arm, and wash/blow tip 70 is removed from hollow tip head 40 by lowering arm 30 to the appropriate height in front of wash/blow tip holder 80, moving wash/blow tip 70 into holder 80, and raising arm 30 so that tip 70 is retained in holder 80. Movable arm 30 is then available for other operations as described below.

[0035] Holder 80 is adapted to closely retain tip 70 in

a single fixed position. Although this can be accomplished in a variety of ways, Figures 1 and 2 illustrate an embodiment in which the neck of tip 70 (see Figure 6 for detailed views of wash/blow tip 70) is closely retained in a press fit segment that forms the upper portion of holder 80. The press fit segment closely retains the stem of tip 70 and prevents it from being removed in an upward direction but allows removal in a forward direction. Thus, movable arm 30 can return to holder 80 and always find the stem of tip 70 available for pick up and further use.

[0036] Figure 3 is another front view of the same embodiment shown in Figures 1 and 2 in which again the movable arm is shown in multiple locations to show positioning of the single movable arm for different reagent-application operations. Again, as in Figure 2, the left-most position is the home position of arm 30. The second position shows arm 30 moved to a location above a pipet tip 90 in a standard pipet tip box 92 that has been positioned onto base (reagent application tip holder) 100. Lowering movable arm 30 presses hollow tip head 40 into a reagent application tip 90 (here a disposable pipet tip) where the pipet tip is retained on hollow tip head 40 by a press fitting in the same manner in which tips are now used on hand-operated repeating pipets. Movable arm 30 is then raised and moved to the third arm position shown in Figure 3, where the pipet tip is lowered into a reagent container 110 held in a fixed location by a reagent container holder 120. By supplying negative pressure through the pipet tip, reagent is withdrawn into the disposable pipet tip 90 for application to appropriate microscope slides. A measured volume of reagent is withdrawn by supplying negative air pressure to hollow tip 40 (i.e., withdrawing air through hollow tip 40). Although an apparatus of the invention can contain an element specifically designed with this operation, the embodiment shown in Figures 1-3 uses a standard liquid dispensing system and the liquid located in the supply line to act as a piston for withdrawing specific volume of air and thus drawing up specific volumes of reagents into reagent tip 90. This part of the apparatus is shown in more detail in Figure 12. Reagent tip 90 is then raised as before and moved as shown in the fourth head position while raised to an appropriate location above a pre-selected microscope slide. At the pre-selected position, shown in the fifth position of movable arm 30, the reagent tip 90 is lowered, and reagent is applied to the slide again using the commercial liquid dispensing system showing in Figure 12 and the liquid retained in the supply line to act as a piston. Reagent can be applied to a single microscope slide 130, or aliquots of the reagent in tip 90 can be applied to different microscope slides.

[0037] After the reagent is added to the last slide, movable arm 30 is returned to a position above drain bin 26, and a solenoid located on movable arm 30 releases reagent tip 90 into drain bin 26 for later removal. Operation of the solenoid is described in later Figures.

[0038] After removal of reagent application tip 90, hollow tip head 40 is again available for further operations.

[0039] Figure 4 is a series of three views of movable arm 30. In the plan view, some of arm 30 is obstructed by the X-axis track 32. However, a portion of arm 30 is visible at the bottom of the plan view, including solenoid 42 that is used for tip removal.

[0040] The front view of Figure 4 shows Z-track 36 and Z-slide 38 which moves along track 36 under control of the Z-axis motor 39 which is visible in the side view of Figure 4C. The side view of Figure 4C also shows X-axis motor 41, along with the X-track 32.

[0041] Operation of tip release solenoid 42 is most apparent from this side view of Figure 4, as activation of the solenoid causes slide member 43 to be moved downward, thereby pressing a retained tip off the end of tip head 40. Slide 43 then returns to its normal position (as shown in this figure) so that another tip can be placed on tip head 40.

[0042] Figure 5 shows three views of the movable arm 30, with the center view showing hollow tip head 40 without having a tip present on the head. In the embodiment shown, tip head 40 has three different diameters at different locations, namely a segment 40a that is sufficiently large to act as a stop when press-fitting a reagent tip 90 onto tip head 40, an intermediate section 40b that acts as the press-fit location for reagent application tip 90, and a smaller-diameter segment 40c at the end of tip head 40 that is sized to fit the wash/blow tip. Thus, as shown in the right-most view of arm 30 in Figure 5, hollow tip head 40 is inserted into wash/blow tip 70 only as far as segment 40c, while the left-most view of Figure 5 shows hollow tip head 40 being inserted into a disposable pipet tip 90 as far as the dividing line between segment 40a and 40b. Thus, the reagent application tip 90 is removed when solenoid 42 moves as far down hollow tip head 40 as segment 40b, with the solenoid slide ring (not visible in this view) simply pushing pipet tip 90 off the end of hollow tip head 40. Solenoid 42 is not used to remove wash/blow head 70, since removing a reusable tip in this manner will not allow easy pickup. Instead, the reusable tip 70 is removed by inserting into a holder as previously described. In preferred embodiments of the invention, the solenoid release mechanism described above is generally used for disposable tips, while a press fitting and specifically designed holder are used for reusable tips so that such tips will be retained in the proper orientation for further use.

[0043] Figure 6 shows a series of three detailed views of wash/blow tip 70. In the front view of Figure 6, solid lines are used to indicate exterior surfaces and dashed lines are used to indicate interior surfaces.

[0044] In the sectional side view of Figure 6A, the hollow interior of tip head 70 is visible, as is the formation of tip head 70 from three parts. It is preferred to have the tip head formed from at least two parts, so that the interior hollow space will be available for cleaning. In the

embodiment shown in Figure 6, three pieces are present: a stem 72, head 74, and a press-fit connector 76. Stem 72 is specifically adapted to be releasably held by holder 80 as previously described. A raised lip 73 is provided at the top of stem 72 which functions in combination with head 74 to act as top and bottom stops, respectively, when stem 72 is pressed into holder 80 as described above in the description of the operation of the wash/blow tip associated with Figure 2.

[0045] The hollow interior of tip 70 is not limited to the specific shape shown, although certain advantages are obtained for aspects of this interior shape and slit shape as described below. In general, the hollow interior 77 of the head can vary significantly in shape as long as sufficient access is provided for easy flow of fluid into interior space 77 so that pressure differentials do not build up and cause differential exit of air or liquids through exit slot 79. Exit slot 79 is generally located on the bottom-most surface of tip 70 and is preferably a linear exit slit having a length substantially equal to the width of a standard microscope slide of the type selected for use at a given time. As there are different sizes of microscope slides, different wash/blow tips 70 can be prepared for each such microscope slide.

[0046] As shown in the sectional side view of Figure 6, access 78 between hollow interior space 77 and exit slit 79 is preferably provided so that air leaving slit 79 exits at an angle to the vertical. By providing air exiting slit 79 at an angle and moving the head in a direction toward the obtuse angle formed between the air wall and the microscope slide, removal of water or buffer from the slide is enhanced.

[0047] Figure 7 shows several typical reagent dispensing patterns on a microscope slide. Most slides have a specimen area 132 and an area for writing information on the slide 134. Because of the nature of the operation of mounting specimens on slides, a tissue sample can be present at any location in area 132. As previously discussed, the thin film of buffer that will be present when staining reagent is added to the slide assists in ensuring that adequate reagent is added to the tissue sample, regardless of where the sample is located or reagent is applied. However, in a preferred embodiment of the apparatus and method, the reagent is dispensed in a pattern rather than a single location so that a distance that a reagent must diffuse through the liquid film is reduced. Several typical reagent dispensing patterns are shown, although other patterns are equally viable.

[0048] Although many staining operations can be carried out without heating the slides, some staining techniques can be enhanced by providing heat so that either incubation or drying times are shortened, thereby increasing the speed of the overall operation. Numerous techniques exist for heating microscope slides and can be adapted to the present apparatus. A preferred embodiment involving such a heater in combination with a microscope slide holder involving a removable tray for

multiple microscope slides is shown beginning in Figure 8. This figure shows six views of tray 190 intended to hold ten standard 1"x 3" (2.5 x 7.5 cm) microscope slides. Tray 190 is formed into a series of individual wells 192 for microscope slides; the location of a single microscope slide 130 is shown by a dotted line in the right-most well of the plan view of Figure 8. For reasons that will become apparent later, the bottom of the individual wells is open; this opening will allow the surface of a heating block to directly contact the bottom of each microscope slide. Individual side walls 194 separate each well 192 from its adjacent wells to prevent accidental contact of liquid (such as might occur during a washing operation). The open bottom of the wells 192 also allows buffer to drain through the bottom of tray 190 where it will be disposed off, typically in a drain pan shown in later figures. The side walls and retaining tabs 196 closely retain microscope slides placed into the individual wells. A gap 198 is present at one end of the well to allow easy grasping of an individual microscope slide between thumb and forefinger for insertion into and removal from tray 190.

[0049] Removable trays 190 are designed from ease of operation by allowing a user to place microscope slides in a loading tray outside the cabinet in which staining operations will occur. The tray also fits precisely into other elements at the appropriate location on base plate 22. However, other embodiments are possible, such as embodiments in which microscope slides are placed directly into permanent wells located inside the supporting framework of the apparatus.

[0050] An individual heating block that will be used with the tray is used in Figure 9. Two views are shown, namely a plan view (9A), and a cross-sectional view (9B). As seen most clearly in the cross-sectional view, the surface of the heating block 200 is divided into a number of raised areas 202 and depressions 204. Depressions 204 are sized to closely fit the bottom edges of slide carrier tray 190. When the bottom edges of tray 190 are placed in these depressions, raised areas 202 press upward into the open bottoms of the wells of the tray and closely contact the individual microscope slides while also acting to precisely locate tray 190 relative to the location of heating block 200.

[0051] Each of the individual heater blocks 200 shown in Figure 9 can be assembled into an array of multiple blocks as shown in Figure 10 using mounting blocks 206 and 207. It is then possible to individually heat each of the heater blocks to different temperatures, thereby concurrently providing different temperatures of operation for different reagent configurations without operator intervention. In the embodiment shown in Figure 1, each of the individual heater blocks is heated electrically for easy temperature control.

[0052] The heater block assemblies can be mounted on a drain pan for ready disposal of wash fluid. Figure 11 shows plan and front sectional views of the heater block assembly shown in Figure 10 mounted on a drain

pan 205 and bearing four microscope slide trays 190, each of which is capable of containing 10 slides for a total of 40 microscope slides in a fixed array. The sides of the microscope slide tray 190 prevent contamination between adjacent microscope slides, and the open bottom of tray 190 and the space between individual heater blocks 200 allow ready draining of wash fluid from the individual microscope slides.

[0053] Figure 12 shows three views of various components used in the supply of air and wash liquid to head 30. Although air can be supplied by a compressed air container and regulator, in the embodiment shown in Figure 1a compressor 170 (and surge reservoir) provides air through flexible line 172 to movable arm 30 and ultimately to hollow tip 40. An air shut-off valve 174 is located in this line and is controlled by control means 150 (not visible in this figure). Buffer or other wash solution is supplied by a component that allows delivery of measured volumes of liquid, such as a commercially available, electrically operated automatic dispensing pipet. Buffer in a reservoir 182 is supplied by supply line 184 to diluter 180 and hence through supply line 186 to movable head 30 and ultimately hollow tip 40. Diluter 180 in the embodiment shown acts as a shut-off valve, so that no further valving is required. Additionally, the liquid present in line 186 is essentially inelastic and acts as a piston for withdrawing or dispensing measured volumes of air through hollow tip 40. For example, during a washing operation as described above, both line 186 and hollow tip 40 on movable head are filled with wash liquid. During the blow operation, air is released by shut-off valve 174 and blows buffer out of hollow tip 40. However, since diluter 180 is shut-off at this time, liquid can not be forced back into diluter 180 through line 186 but is retained in line 186. After the completion of a blow operation and pick up of a reagent dispensing tip 90 onto hollow tip head 40, the next operation will be withdrawal of reagent from a reagent container into pipet tip 90. Thus, even if the amount of liquid retained in line 186 is slightly variable, the next operation is withdrawing of liquid further into line 186 by a precise amount under the control of controller 150 and diluter 180, so that the actual amount of liquid present in supply line 186 makes no difference in the measurement operation. Likewise, in the dispensing of the aliquots of reagent on individual slides, wash liquids will not be expelled from line 186, since no more liquid will be returned to line 186 by diluter 180 than was originally withdrawn. Thus, diluter 180 and the liquid present in line 186 operate to supply the desired negative and positive air pressure for dispensing reagent to the individual slides.

[0054] As will be apparent from the operation as described above, a valve 188 is present as part of diluter 180 so that the diluter withdraws and dispenses liquid through the appropriate line 184 or 186 for different operations.

[0055] It will be apparent to one of ordinary skill that many of the specific elements shown in the figures and

described above can be replaced by other elements that perform the same function. For example, the XYZ tracks can be replaced by a single robotic arm. Additionally, it will be understood that the specific tracks, motors, and other individual parts can be replaced by other parts of equivalent function. In a preferred embodiment of the invention, the XYZ tracks were purchased as commercially available sliding tracks. The X-axis and Z-axis motions are supplied by a linear motion rail and linear motion guide (Part No. SR20W from THK) and a stepping motor (Part No. 4023-819 for the X-axis and 5017-009 for the Z-axis, both supplied by Applied Motion). The two rails of the Y-axis shaft system are a linear bearing rail assembly (Part No. SRA-8-XS) and linear bearing pillow block (Part No. SPB-8-OPN-XS), both supplied by Thomson; power along the Y-axis was supplied by the same stepping motor used for the X-axis. Other commercially available components used in the embodiment shown in Figures 1-3 include a Thomas Industries, Inc. Model No. 107CA18 compressor, a Cavro XL-3000 automatic diluter and a NAC Valves, Inc., Model No. 35A-AAA-0AAA-IBA air shut-off valve. Electrical connections, tubing, compressed air distribution systems, liquid distribution systems from a central reservoir, and many other components such as holders for a standard pipet tip box or for reagent containers are commercially available from a variety of suppliers. Thus, the apparatus of the invention can be prepared from readily available commercial parts assembled in the manner described, with a minimum number of specific manufacturing techniques. Since the blow-dry head (70 in the figures) is not readily available, it will typically be manufactured for a particular apparatus as shown or in a similar manner to provide the features that are described in the specification above.

[0056] The composition of the components from which various parts are manufactured can vary widely, but components through which reagents pass or which contact potentially corrosive reagent or wash solutions are typically prepared from stainless steel or inert plastics to prevent corrosion. The wash/blow head is typically formed from a moldable plastic (such as a polyacrylate) and can be prepared by a molding process, a plastic-shaping process, or some combination thereof depending on the individual shape chosen by a user. Parts that are subject to wear, such as the stem of the wash/blow head 70 and hollow tip head 40 are typically prepared from a hard plastic or other material that will resist wear.

[0057] The apparatus is typically operated under the control of a computer or other programmable control device. In the simplest applications where only a single type of automated staining will be done repeatedly, it is possible to provide either a hard-wired controller or a non-programmable electronic controller, such as a computer operating under instructions from read-only memory. In preferred embodiments, however, a programmable controller or computer is used so that the operation can be varied. Software will generally be pro-

vided with the computer so that the user does not need to provide instructions for individual motions, but merely selects appropriate motions from a menu. In a typical operation, a user would be asked to select the location and volume of the reagents, the location of the slides being treated, and the length of time of various steps such as incubation times (and if necessary the temperature); all other operations will be carried out by the pre-programmed instruction set in the memory of the computer, which will control actual movement of the movable arm to the appropriate locations and activation of the various air and liquid control systems.

[0058] A key step in the method that is used in the automated apparatus of the invention involves blowing excess reagent or buffer off the surface of the slide. A preferred embodiment of the tip used in this blowing operation is shown in Figure 6, although other tips having slits for exit of air to provide a wall of air can also be used. By adjusting the air pressure, height of the exit slit above the microscope slide, and rate of movement of the slit, the extent to which liquid is removed from the slide can be varied. The amount of liquid present in the thin film on the microscope slides upper surface is quite small, typically being from 2 to 25 microliters, more generally from 3 to 20, and preferably from 5 to 10. The area of concern is approximately 15 cm², providing a typical volume per surface area of 0.13 to 1.7 microliter/cm². However, it is difficult to determine the actual volume being used, since the operation of blowing liquid off the top surface of a slide causes liquid to adhere to other portions of the microscope slide, making measurement of the remaining liquid difficult. Thus, the volume of liquid present on the slide upper surface at the end of a blow-dry operation is best determined empirically. The maximum permissible volume is determined by the stain being used and its concentration at the reagent application stage, since these factors affect the final concentration of the stain or other reagent on the surface of this slide. Historical procedures developed for slide preparation are generally described in terms of a particular reagent concentration, incubation time, and temperature. Accordingly, it is desirable to provide a minimum volume of liquid on the slide in order to avoid having to change the concentration of reagents from the standard used in the industry. By adhering to this guideline, it is possible to use commercially available, already prepared stain solutions as reagents.

[0059] On the other hand, too little liquid on a slide can cause problems in reagent spreading, particularly because of evaporation. Since buffer is added to a slide prior to addition of reagent and motion of the moveable arm to pick up reagent application tips and reagents takes time, the buffer must remain on the slide until reagent is added, which further may not occur until after preparation of other slides. Since it is more efficient to prepare multiple slides at one time rather than to require repeated movements of the movable arm and repeated pickup motions for the various heads, a typical minimum

volume of buffer would be that amount which is sufficient to allow preparation of about four slides without requiring removal of a given tip.

[0060] The air pressure, height of the head above the slide, and rate of motion of the head for control of the liquid film can all be selected by the user or by the manufacturer of the apparatus. Generally, the same air pressure will be used at all time so as to remove this variable from consideration. Thus, only the height of the head and the rate of motion will typically be varied. The higher the height of the head above the slide, the less liquid is removed. The faster the head is passed across the slide for a given height, the less liquid is removed.

[0061] For a standard 1 inch by 3 inch (2.5 X 7.5 cm) microscope slide surface area and a wash/blow tip having the configuration shown in Figure 6, an air pressure of 7 psi (0.5 atm.), a height of 0.07 inch (2 mm) above the microscope slide surface, and a rate of motion of 3 inch/sec (7.5 cm/sec) provide a preferred buffer film suitable for the staining of 4 slides at 25°C and a relative humidity of 60-80%, which is the typical humidity present inside a closed and operating apparatus of the invention.

[0062] The wash solutions used in the apparatus of the invention can vary significantly depending on the staining technique being used. A typical wash solution is an aqueous solution of a surfactant and can contain other components present in typical slide preparation of wash solutions, such as buffers. In preferred embodiments, sufficient surfactant is present to provide a surface tension in a solution equivalent to that present in solutions containing water in the following surfactants at the concentrations listed. Typical surfactants used (with concentrations shown in parenthesis) are TWEEN 20 (0.02 to 2% v/v), BRIT 35 (0.05 to 2% v/v), and TRITON X-100 (0.01 to 1% v/v). Typical buffers used (with pH shown in parenthesis) are phosphate buffered saline (7.6) and TRIS-CL (7.6). For conciseness of language, the specification and claims often referred to water as the wash fluid or the fluid being removed at a particular step. It will be apparent that this "water" can and generally is an aqueous solution of buffer and surfactant or of some staining reagent.

[0063] It will be apparent that the apparatus and method of the invention can be used in any staining technique that can be carried out manually and that there are no limitations placed on the invention by the staining technique.

[0064] The apparatus of the invention can contain a number of further components designed for ease of operation. For example, drain trays with exit lines to waste reservoirs can be located either individually under components of the apparatus or a single drain tray and collection system can be provided for the entire interior space of the apparatus frame. In a typical apparatus, the frame is a form of a cabinet with an interior space in which all operations take place. A closable access port (e.g., door) is provided to allow an operator

5 to add the various removable components to the interior cabinet space. A transparent door can be provided to prevent accidental spilling of liquid (as during a drying operation) into the room in which the apparatus is located while allowing the operator of the apparatus to visually verify correct operation. Other optional features that can be included on the apparatus include devices intended to ensure level operation, to protect against electric shock, to verify that an appropriate tip has been selected and properly placed on the tip head, or to optically scan slides in a microscope slide tray or other container for microscope slides so that a human operator does not even need to enter information into the computer. Such information could be provided, for example, by a standard bar code attached to an individual microscope slide reagent container or other component. Multiple reagent containers can be provided so that different staining operations can be carried out under control of the bar code and the computer and its pre-program software.

Claims

1. An automated staining apparatus (10), comprising:

25 a supporting framework (20);
 an arm (30) moveable in three dimensions attached to said framework (20);
 means for moving said arm;
 30 a hollow tip head (40) located on said arm;
 means for alternatively supplying positive or negative gas pressure to said hollow tip head;
 a removable wash/blow tip (70) having an exit slit substantially equal in length to the width of a microscope slide (130), said wash/blow tip (70) being adapted to be removably attached to said hollow tip head (40) by a preselected movement of said arm;
 35 a wash/blow tip holder (80) at a first fixed location on said framework;
 a reagent application tip holder (100) at a second fixed location on said framework for holding a reagent application tip (90), said reagent application tip being adapted to be removably attached to said hollow tip head by a preselected movement of said arm (30);
 40 a reagent container holder (120) at a third fixed location on said framework (20);
 a microscope slide holder (140) at a fourth fixed location on said framework (20), said microscope slide holder being adapted to removably contain said microscope slide (130);
 45 and
 control means for controlling movement of said arm between said locations, whereby said tip head (40) picks up said wash/blow tip or said reagent application tip (90) in response to movement of said arm 30 under control of said

- control means and moves to one or more of said locations to ~~pick up~~ a reagent in said reagent container or dispense said reagent on said slide or to dispense a gas or a liquid through said wash/blow tip over said slide.
2. The apparatus of claim 1, wherein said supporting framework (20) comprises a cabinet having an interior space and all of said locations are in said interior space.
 3. The apparatus of claim 1, wherein said cabinet has a closeable access port.
 4. The apparatus of claim 1, wherein said arm (30) moves along independent X, Y and Z tracks for independent movement of said tip head (40) in three orthogonal directions.
 5. The apparatus of claim 1, wherein said arm (30) remains in a fixed location in the absence of power being supplied to said means for moving said arm.
 6. The apparatus of claim 1, wherein said X and Y tracks are oriented in the horizontal plane of said apparatus when said apparatus is in its normal operating orientation.
 7. The apparatus of claim 1, wherein said apparatus further comprises a liquid reservoir in selectable fluid communication with said hollow tip head (40).
 8. The apparatus of claim 1, wherein said means for supplying gas pressure comprises a pressurized gas reservoir or compressor (170).
 9. The apparatus of claim 1, wherein said means for supplying gas pressure is capable of withdrawing or dispensing a fixed amount of gas through said tip head (40), said fixed amount being selectable by said control means, thereby providing measured withdrawing or dispensing of a liquid into or from a reagent application tip attached to said hollow tip head.
 10. The apparatus of claim 9, wherein said means for supplying gas pressure comprises a moveable piston that controls liquid in a liquid supply line between a liquid reservoir and said hollow tip head (40).
 11. The apparatus of claim 10, wherein said means for supplying gas pressure comprises a pressurized gas reservoir or compressor, said moveable piston, and means for alternatively selecting said reservoir or said piston for dispensing or withdrawing of gas through said tip head (40).
 12. The apparatus of claim 1, wherein said wash/blow tip (70) is attached to said hollow tip head (40) via a press fitting.
 - 5 13. The apparatus of claim 12, wherein said wash/blow tip holder (80) is adapted to release said wash/blow tip (70) from said holder when said tip head (40) is pressed by said arm (30) onto said wash/blow tip (70) and said tip head (40) is withdrawn from said holder in a first direction relative to said holder.
 - 10 14. The apparatus of claim 12, wherein said wash/blow tip holder (80) is adapted to remove said wash/blow tip (70) from said tip head (40) when said wash/blow tip on said tip head is inserted into said wash/blow tip holder (80) and said tip head is withdrawn from said holder in a second direction relative to said holder.
 - 15 20 15. The apparatus of claim 1, wherein said reagent application tip holder (100) is adapted to retain a container of disposable tips (90), whereby said tips are retained by said container as an array of tips at a fixed orientation for access by said tip head.
 - 25 30 16. The apparatus of claim 1, further comprising one or more additional holders for reagent containers at fixed locations on said framework.
 - 35 35 17. The apparatus of claim 1, wherein said apparatus further comprises a heater (200) for microscope slides at said fourth location.
 - 40 45 18. The apparatus of claim 1, wherein said apparatus further comprises a removable microscope tray (190) adapted to retain multiple microscope slides in a fixed array at said fourth location.
 - 40 40 19. The apparatus of claim 18, wherein said tray (190) comprises individual wells for microscope slides and said wells are partially open on their bottom surfaces.
 - 45 50 20. The apparatus of claim 19, further comprising a microscope slide heating surface, wherein when said tray (190) with any microscope slides contained in said tray is inserted into said microscope slide holder (140), said microscope slides contact said heating surface through the partially open bottom surface of said wells.
 - 55 21. The apparatus of claim 20, wherein individual segments of said heating surface are controlled by said control means, thereby providing different temperatures for said segments.
 22. The apparatus of claim 1, wherein said control means comprises a programmable computer.

23. The apparatus of claim 1, wherein said control means causes a gas to be blown through said wash/blow tip as said wash/blow tip is moved horizontally over said microscope slide.

24. The apparatus of claim 1, wherein said control means causes a reagent tip (90) on said tip head (40) to withdraw and hold for transfer a fixed volume of said reagent from said container, then causes said tip head (40) to move to a location above a microscope slide (130) in said microscope slide holder (140), and then causes said reagent tip (90) to dispense a fixed volume of said reagent on said microscope slide (130).

25. A method for applying a water-soluble tissue reagent to a microscope slide having a tissue specimen mounted thereon, which method comprises:

applying a film of water to a horizontal upper surface of said slide; and

applying said reagent to said film of water in a pattern insufficient to fully cover said slide surface when said slide is dry, whereby said reagent diffuses through said film to reach substantially all of said surface.

26. The method of claim 25, wherein said film has a volume of from 0.13 to 1.7 microliters per square centimeter of surface

27. The method of claim 25, wherein said water contains dissolved or suspended non-water components.

28. The method of claim 27, wherein said water contains a surfactant.

29. The method of claim 28, wherein said water further contains a buffer.

30. A method for staining a tissue on a microscope slide, which comprises:

applying excess water to a microscope slide oriented to have a horizontal surface bearing said tissue;

removing water from said slide by blowing a gas across said horizontal surface through a slit while said slit is moved horizontally across said surface in proximity to said surface, thereby leaving a film of water on said surface;

applying a reagent to said surface in a stream or intermittently in a pattern adapted to allow said reagent to diffuse throughout said film of water, said pattern being insufficient to fully cover said surface when said surface is dry; and

allowing said reagent to stain said tissue on said surface.

31. A wash/blow tip for an automated staining apparatus, which comprises:

a hollow body member formed of at least two detachable parts having an internal cavity which is accessible when said parts are detached;

a linear exit slit providing fluid communication between said internal cavity and the external environment surrounding said tip, said linear exit slit being adapted to be substantially identical in length to the width of a microscope slide;

means for removably attaching said hollow body member to a tip head in said apparatus and providing access to said internal cavity for gas or liquid supplied through said tip head.

32. The tip of claim 31, wherein said means for removably attaching comprises a hollow tube communicating with said internal cavity and adapted to be connected by a press fit to said tip head.

Patentansprüche

1. Automatischer Einfärbungsapparat (10) mit:

einem Halterahmen (20);

einem Arm (30), der in drei Dimensionen bewegbar am Rahmen (20) befestigt ist;

Mitteln zum Bewegen des Arms;

einem am Arm angeordneten Hohlspitzenkopf (40);

Mitteln zum abwechselnden Zuführen von positivem oder negativem Gasdruck zum Hohlspitzenkopf;

einer auswechselbaren Wasch/Blas-Spitze (70) mit einem Ausgangsschlitz im wesentlichen mit einer Länge gleich der Breite des Mikroskopobjektträgers (130), wobei die Wasch/Blas-Spitze (70) so ausgebildet ist, daß sie mittels einer vorgewählten Bewegung des Arms an dem Hohlspitzenkopf (40) lösbar befestigbar ist;

einem Wasch/Blas-Spitzenhalter (80) an einem ersten feststehenden Ort am Rahmen;

einem Reagenz-Aufbringspitzenhalter (100) an einem zweiten feststehenden Ort am Rahmen

- zum Halten einer Reagenzaufbringspitze (90); wobei die Reagenzaufbringspitze (90) so ausgebildet ist, daß sie an dem Hohlspitzenkopf durch eine vorgewählte Bewegung des Arms (30) lösbar befestigbar ist;
- 5 einem Reagenzbehälterhalter (120) an einem dritten feststehenden Ort am Rahmen (20);
- einem Mikroskopobjektträgerhalter (140) an einem vierten feststehenden Ort am Rahmen (20), wobei der Mikroskop-Objekträgerhalter so ausgebildet ist, daß er den Mikroskop-Objekträger (130) auswechselbar enthalten kann; und
- 10 einer Steuerung zum Steuern der Bewegung des Arms zwischen den Orten, so daß der Spitzkopf (40) die Wasch/Blas-Spitze oder die Reagenzaufbringspitze (90) in Antwort auf die Bewegung des Arms (30), gesteuert durch die Steuerung, aufnimmt und an einen oder mehrere Orte bewegt, um ein Reagenz in den Reagenzbehälter aufzunehmen oder das Reagenz auf den Objekträger auszugeben oder ein Gas oder eine Flüssigkeit durch die Wasch/Blas-Spitze über dem Objekträger auszugeben.
- 15
- 20 2. Apparat nach Anspruch 1, wobei der Halterrahmen (20) eine Kabine mit einem Innenraum aufweist, und alle besagten Orte in dem Innenraum angeordnet sind.
- 25 3. Apparat nach Anspruch 1, wobei die Kabine eine schließbare Zugangsöffnung hat.
- 30 4. Vorrichtung nach Anspruch 1, wobei der Arm (30) entlang unabhängiger X-, Y- und Z-Schienen für eine unabhängige Bewegung des Spitzkopfes (40) in drei rechtwinklig aufeinander stehenden Richtungen läuft.
- 35 5. Apparat nach Anspruch 1, wobei der Arm (30) bei Abwesenheit von Zufuhr von Leistung zu der Einrichtung zum Bewegen des Arms an einem feststehenden Ort bleibt.
- 40 6. Apparat nach Anspruch 1, wobei die X- und Y-Schienen in der Horizontalebene des Apparates ausgerichtet sind, wenn der Apparat in seiner normalen Betriebsausrichtung ist.
- 45 7. Apparat nach Anspruch 1, wobei der Apparat weiterhin einen Flüssigkeitsvorratsbehälter in wählbarer Fluidkommunikation mit den Hohlspitzenkopf (40) aufweist.
- 50 8. Apparat nach Anspruch 1, wobei die Einrichtung zum Zuführen von Gasdruck einen Druckgas-Vorratsbehälter, einen Kompressor (170) aufweist.
- 55 9. Apparat nach Anspruch 1, wobei die Einrichtung zum Zuführen von Druckgas eine feststehende Menge Gas durch den Spitzkopf (40) ziehen oder freigeben kann, wobei die feststehende Menge durch die Steuerung wählbar ist, wodurch eine bemessene Menge Flüssigkeit von einer Reagenz-Aufbringspitze, die am Hohlspitzenkopf befestigt ist, abgezogen oder freigegeben wird.
10. Apparat nach Anspruch 9, wobei die Einrichtung zum Zuführen von Druckgas einen bewegbaren Kolben hat, der die Flüssigkeit in einer Flüssigkeitsversorgungsleitung zwischen dem Flüssigkeitsvorratstank und dem Hohlspitzenkopf (40) steuert.
11. Apparat nach Anspruch 10, wobei die Einrichtung zum Zuführen von Druckgas einen Druckgas-Vorratstank oder Kompressor aufweist, wobei bewegbare Kolben und die Einrichtung zum abwechselnden Wählen des Vorratstanks oder des Kolbens dazu dienen, Gas durch den Spitzkopf (40) freizugeben oder herauszuziehen.
12. Apparat nach Anspruch 1, wobei die Wasch/Blas-Spitze (70) an dem Hohlspitzenkopf (40) über eine Preßpassung befestigt ist.
13. Apparat nach Anspruch 12, wobei der Wasch/Blas-Spitzenhalter (80) so ausgebildet ist, daß er die Wasch/Blas-Spitze (70) am Halter freigibt, wenn der Spitzkopf (40) vom Arm (30) auf die Wasch/Blas-Spitze (70) gedrückt wird, und der Spitzkopf (40) vom Halter in einer ersten Richtung relativ zum Halter abgezogen wird.
14. Apparat nach Anspruch 12, wobei der Wasch/Blas-Spitzenhalter (80) so ausgebildet ist, daß die Wasch/Blas-Spitze (70) vom Spitzkopf (40) entfernt werden kann, wenn die Wasch/Blas-Spitze (70) an den Spitzkopf in den Wasch/Blas-Spitzenhalter (80) eingesetzt ist, und der Spitzkopf vom Halter in einer zweiten Richtung relativ zum Halter abgezogen werden kann.
15. Apparat nach Anspruch 1, wobei der Reagenz-Aufbringspitzenhalter (100) so ausgebildet ist, daß er einen Behälter verfügbarer Spitzen (90) zurückhält, wodurch die Spitzen durch den Behälter als ein Feld von Spitzen in einer festliegenden Ausrichtung für den Zugriff durch den Spitzkopf zurückgehalten werden.
16. Apparat nach Anspruch 1, weiterhin mit einem oder mehreren zusätzlichen Haltern für Reagenzbehälter an feststehenden Orten am Rahmen.

17. Apparat nach Anspruch 1, wobei der Apparat weiterhin eine Heizeinrichtung (10) für Mikroskopobjekträger an dem vierten Ort aufweist.
18. Apparat nach Anspruch 1, wobei der Apparat weiterhin einen auswechselbaren Mikroskoptröpfchen (190) hat, der so ausgebildet ist, daß er eine Vielzahl von Mikroskop-Objekträgern in einem ersten Feld des vierten Ortes halten kann.
19. Apparat nach Anspruch 18, wobei der Trog (190) individuelle Wannen für Mikroskop-Objekträger hat und die Wannen teilweise an ihrer Unterseite offen sind.
20. Apparat nach Anspruch 19, weiterhin mit einer Mikroskop-Objekträger-Heizfläche, wobei, wenn der Trog (190) mit irgendwelchen Mikroskop-Objekträgern in dem Trog in den Mikroskop-Objekträgerhalter (140) eingesetzt wird, die Mikroskop-Objekträger die Heizfläche über die teilweise offene Bodenfläche der Wannen kontaktiert.
21. Apparat nach Anspruch 20, wobei einzelne Segmente der Heizfläche durch die Steuerung gesteuert werden, wobei für die Segmente unterschiedliche Temperaturen geschaffen werden.
22. Apparat nach Anspruch 1, wobei die Steuerung einen programmierbaren Computer aufweist.
23. Apparat nach Anspruch 1, wobei die Steuerung bewirkt, daß Gas durch die Wasch/Blas-Spitze geblasen wird, wenn die Wasch/Blas-Spitze horizontal über den Mikroskop-Objekträger bewegt wird.
24. Apparat nach Anspruch 1, wobei die Steuerung bewirkt, daß eine Reagenzspitze (90) an dem Spitzenkopf (40) ein feststehendes Volumen des Reagenz aus dem Behälter zieht und für den Transport hält, dann bewirkt, daß der Spitzenkopf (40) zu einem Ort oberhalb eines Mikroskop-Objekträgers (130) in dem Mikroskop-Objekträgerhalter (140) läuft, und dann bewirkt, daß die Reagenzspitze (90) ein feststehendes Volumen des Reagenz auf den Mikroskop-Objekträger (130) freigibt.
25. Verfahren zum Aufbringen eines wasserlöslichen Gewebereagenz auf einen Mikroskop-Objekträger, auf welchem Gewebeproben aufgebracht sind, wobei das Verfahren aufweist:
- Aufbringen eines Wasserfilms auf eine horizontale obere Fläche des Objekträgers; und
- Aufbringen des Reagenz auf den Wasserfilm in einem Muster, das nicht ausreicht, die Objekt-
- träger-Oberfläche vollständig zu bedecken, wenn der Objekträger trocken ist, wodurch das Reagenz durch den Film diffundiert, um im wesentlichen die gesamte Oberfläche zu erreichen.
26. Verfahren nach Anspruch 25, wobei der Film ein Volumen von 0,13 bis 1,7 Mikroliter pro Quadratzentimeter Oberfläche hat.
27. Verfahren nach Anspruch 25, wobei das Wasser nichtwässrige Komponenten gelöst oder suspenziert enthält.
28. Verfahren nach Anspruch 27, wobei das Wasser einen grenzflächenaktiven Stoff enthält.
29. Verfahren nach Anspruch 28, wobei das Wasser weiterhin einen Puffer enthält.
30. Verfahren zum Einfärben eines Gewebes auf einem Mikroskop-Objekträger, mit:
- Aufbringen von überschüssigem Wasser auf einen Mikroskop-Objekträger, der so ausgerichtet ist, daß er eine horizontale Oberfläche hat, auf der das Gewebe liegt;
- Entfernen des Wassers von dem Objekträger durch Blasen eines Gases über die horizontale Fläche durch einen Schlitz, während der Schlitz horizontal über die Fläche in der Nähe der Fläche bewegt wird, wobei auf der Fläche ein Wasserfilm verbleibt;
- Aufbringen eines Reagenz auf die Oberfläche in einem Strom oder intermittierend in einem Muster, das so ausgebildet ist, daß es ein Diffundieren des Reagenz durch den Wasserfilm erlaubt, wobei das Muster nicht ausreicht, die Oberfläche vollständig zu bedecken, wenn die Oberfläche trocken ist; und
- Zulassen, daß das Reagenz das Gewebe auf der Oberfläche färbt.
31. Wasch/Blas-Spitze für einen automatischen Einfärbungsapparat, mit:
- einem Hohlkörperlement, das aus wenigstens zwei lösbarer Teilen besteht, die einen Innenhohlraum haben, der zugänglich ist, wenn die Teile gelöst sind;
- einem linearen Ausgangsschlitz, der eine Fluidkommunikation zwischen dem Innenhohlraum und der Außenumgebung, welche die Spitze umgibt, schafft, wobei der lineare Aus-

gangsschlitz so ausgebildet ist, daß er im wesentlichen eine ~~tête~~ hat, die identisch mit der Breite eines Mikroskop-Objektträgers ist;

einer Einrichtung zum entfernbaren Befestigen des Hohlkörperelements an einem Spitzenkopf in dem Apparat und Vorsehen eines Zugangs zum Innenhohlraum für Gas oder Flüssigkeit, die durch den Spitzenkopf zugeführt werden.

32. Spitze nach Anspruch 31, wobei die Einrichtung zum lösbar Befestigen eine hohle Röhre aufweist, die mit dem Innenhohlraum in Verbindung steht, und so ausgebildet ist, daß sie durch eine Presspassung mit dem Spitzenkopf verbunden werden kann.

Revendications

1. Appareil automatisé (10) de coloration comportant :

un bâti (20) de support ;
 un bras (30) mobile dans trois dimensions et relié audit bâti (20) ;
 des moyens destinés à déplacer ledit bras ;
 une tête (40) à embout creux placée sur ledit bras ;
 des moyens destinés à appliquer alternativement une pression gazeuse positive ou négative à ladite tête à embout creux ;
 un embout amovible (70) de lavage/soufflage ayant une fente de sortie de longueur sensiblement égale à la largeur d'une lame porte-objet (130) de microscope, ledit embout (70) de lavage/soufflage étant conçu pour être relié de façon amovible à ladite tête (40) à embout creux par un mouvement préalablement choisi dudit bras ;
 un support (80) d'embout de lavage/soufflage dans un premier emplacement fixe sur ledit bâti ;
 un support (100) d'embout d'application de réactif en un second emplacement fixe sur ledit bâti pour porter un embout (90) d'application de réactif, ledit embout d'application de réactif étant conçu pour être relié de façon amovible à ladite tête à embout creux par un mouvement préalablement choisi dudit bras (30) ;
 un support (120) de récipient à réactif en un troisième emplacement fixe sur ledit bâti (20) ;
 un support (140) de lame porte-objet de microscope en un quatrième emplacement fixe sur ledit bâti (20), ledit support de lame porte-objet de microscope étant conçu pour contenir de façon amovible ladite lame porte-objet (130) du microscope ; et
 des moyens de commande destinés à com-

mander un mouvement dudit bras entre lesdits emplacements, grâce à quoi ladite tête à embout ~~(40)~~ prend ledit embout de lavage/soufflage ou ledit embout (90) d'application de réactif en réponse à un mouvement dudit bras (30) sous la commande desdits moyens de commande et passe par un ou plusieurs desdits emplacements pour prendre un réactif dans ledit récipient à réactif ou distribuer ledit réactif sur ladite lame porte-objet ou distribuer un gaz ou un liquide à travers ledit embout de lavage/soufflage au-dessus de ladite lame porte-objet.

- 15 2. Appareil selon la revendication 1, dans lequel ledit bâti de support (20) comporte un coffret ayant un espace intérieur et tous lesdits emplacements sont situés dans ledit espace intérieur.
- 20 3. Appareil selon la revendication 1, dans lequel ledit coffret présente une ouverture d'accès pouvant être fermée.
- 25 4. Appareil selon la revendication 1, dans lequel ledit bras (30) se déplace le long de chemins X, Y et Z indépendants pour un mouvement indépendant de ladite tête (40) à embout dans trois directions orthogonales.
- 30 5. Appareil selon la revendication 1, dans lequel ledit bras (30) reste dans un emplacement fixe en l'absence d'application d'énergie auxdits moyens destinés à déplacer ledit bras.
- 35 6. Appareil selon la revendication 1, dans lequel lesdits chemins X et Y sont orientés dans le plan horizontal dudit appareil lorsque ledit appareil est dans son orientation normale de fonctionnement.
- 40 7. Appareil selon la revendication 1, dans lequel ledit appareil comporte en outre un réservoir de liquide en communication de fluide, pouvant être choisi, avec ladite tête (40) à embout.
- 45 8. Appareil selon la revendication 1, dans lequel lesdits moyens destinés à appliquer une pression gazeuse comprennent un réservoir ou compresseur (170) de gaz comprimé.
- 50 9. Appareil selon la revendication 1, caractérisé en ce que lesdits moyens destinés à fournir un gaz sous pression sont capables de prélever ou de distribuer une quantité fixe de gaz à travers ladite tête (40) à embout, ladite quantité fixe pouvant être choisie par lesdits moyens de commande, réalisant ainsi un prélèvement ou une distribution mesuré d'un liquide dans ou à partir d'un embout d'application de réactif relié à ladite tête à embout creux.

10. Appareil selon la revendication 9, dans lequel lesdits moyens destinés à appliquer une pression gazeuse comprennent un piston mobile qui commande un liquide dans une conduite d'alimentation en liquide entre un réservoir de liquide et ladite tête (40) à embout creux.
11. Appareil selon la revendication 10, dans lequel lesdits moyens destinés à appliquer une pression gazeuse comprennent un réservoir ou compresseur de gaz comprimé, ledit piston mobile, et des moyens destinés à sélectionner alternativement ledit réservoir ou ledit piston pour distribuer ou prélever du gaz à travers ladite tête (40) à embout.
12. Appareil selon la revendication 1, dans lequel ledit embout (70) de lavage/soufflage est relié à ladite tête (40) à embout creux au moyen d'un ajustement serré.
13. Appareil selon la revendication 12, dans lequel ledit support (80) de l'embout de lavage/soufflage est conçu pour libérer ledit embout (70) de lavage/soufflage dudit support lorsque ladite tête (40) à embout est poussée par ledit bras (30) sur ledit embout (70) de lavage/soufflage et que ladite tête (40) à embout est retirée dudit support dans une première direction par rapport audit support.
14. Appareil selon la revendication 12, dans lequel ledit support (80) d'embout de lavage/soufflage est conçu pour enlever ledit embout (70) de lavage/soufflage de ladite tête (40) à embout lorsque ledit embout de lavage/soufflage situé sur ladite tête à embout est introduit dans ledit support (80) d'embout de lavage/soufflage et que ladite tête à embout est retirée dudit support dans une seconde direction par rapport audit support.
15. Appareil selon la revendication 1, dans lequel ledit support (10) de l'embout d'application de réactif est conçu pour retenir un récipient d'embouts jetables (90), grâce à quoi lesdits embouts sont retenus par ledit récipient sous la forme d'une rangée d'embouts dans une orientation fixe pour que ladite tête à embout puisse y accéder.
16. Appareil selon la revendication 1, comportant en outre un ou plusieurs supports supplémentaires pour des récipients à réactifs dans des emplacements fixes sur ledit bâti.
17. Appareil selon la revendication 1, dans lequel ledit appareil comporte en outre un élément chauffant (200) pour des lames porte-objet de microscope dans ledit quatrième emplacement.
18. Appareil selon la revendication 1, dans lequel ledit appareil comporte en outre un plateau amovible (190) pour microphone conçu pour retenir des lames porte-objet multiples pour microscope en une rangée fixe dans ledit quatrième emplacement.
19. Appareil selon la revendication 18, dans lequel ledit plateau (190) comporte des alvéoles individuels pour lames porte-objet de microscope et lesdits alvéoles sont partiellement ouverts à leurs surfaces inférieures.
20. Appareil selon la revendication 19, comportant en outre une surface de chauffage de lames porte-objet de microscope, dans lequel, lorsque ledit plateau (190) contenant des lames porte-objet de microscope est introduit dans ledit support (140) pour lames porte-objet de microscopie, lesdites lames porte-objet de microscope entrent en contact avec ladite surface chauffante à travers la surface inférieure partiellement ouverte desdits alvéoles.
21. Appareil selon la revendication 20, dans lequel des segments individuels de ladite surface chauffante sont commandés par lesdits moyens de commande, établissant ainsi des températures différentes pour lesdits segments.
22. Appareil selon la revendication 1, dans lequel lesdits moyens de commande comprennent un ordinateur programmable.
23. Appareil selon la revendication 1, dans lequel lesdits moyens de commande provoquent le soufflage d'un gaz à travers ledit embout de lavage/soufflage pendant que ledit embout de lavage/soufflage est déplacé horizontalement au-dessus de ladite lame porte-objet de microscope.
24. Appareil selon la revendication 1, dans lequel lesdits moyens de commande amènent un embout à réactif (90) sur ladite tête (40) à embout à prélever et maintenir, pour un transfert, un volume fixe dudit réactif à partir dudit récipient, puis amènent ladite tête (40) à embout à se déplacer jusqu'à un emplacement situé au-dessus d'une lame porte-objet (130) pour microscope dans ledit support (140) de lame porte-objet de microscope, puis amènent ledit embout (90) à réactif à distribuer un volume fixe dudit réactif sur ladite lame porte-objet (130) de microscope.
25. Procédé pour appliquer un réactif hydrosoluble pour tissus à une lame porte-objet de microscope sur laquelle un échantillon de tissu est monté, lequel procédé comprend :

l'application d'un film d'eau sur une surface supérieure horizontale de ladite lame porte-

objet ; et

l'application dudit réactif sur ledit film d'eau en une configuration insuffisante pour recouvrir complètement ladite surface de la lame porte-objet lorsque ladite lame porte-objet est sèche, grâce à quoi ledit réactif se diffuse à travers ledit film pour atteindre sensiblement la totalité de ladite surface.

5

26. Procédé selon la revendication 25, dans lequel ledit film présente un volume allant de 0,13 à 1,7 microlitres par centimètre carré de surface.

10

27. Procédé selon la revendication 25, dans lequel ladite eau contient, en dissolution ou en suspension, des constituants non aqueux.

15

28. Procédé selon la revendication 27, dans lequel ladite eau contient un surfactant.

20

29. Procédé selon la revendication 28, dans lequel ladite eau contient en outre une substance tampon.

30. Procédé pour colorer un tissu sur une lame porte-objet de microscope, qui comprend :

25

l'application d'un excès d'eau à une lame porte-objet de microscope orientée de façon à avoir une surface horizontale portant ledit tissu

30

à enlever de l'eau de ladite lame porte-objet en soufflant un gaz sur ladite surface horizontale à travers une fente pendant que ladite fente est déplacée horizontalement au-dessus de ladite surface à proximité de ladite surface, laissant ainsi un film d'eau sur ladite surface ;

35

l'application d'un réactif sur ladite surface en un courant ou par intermittence suivant une configuration conçue pour permettre audit réactif de se diffuser à travers ledit film d'eau, ladite configuration étant insuffisante pour recouvrir complètement ladite surface lorsque ladite surface est sèche ; et

40

la possibilité pour ledit réactif de colorer ledit tissu sur ladite surface.

45

31. Embout de lavage/soufflage pour un appareil automatisé de coloration, qui comporte :

un élément de corps creux formé d'au moins deux parties séparables ayant une cavité intérieure qui est accessible lorsque lesdites parties sont séparées ;

50

une fente linéaire de sortie établissant une communication de fluide entre ladite cavité intérieure et l'environnement extérieur entourant ledit embout, ladite fente linéaire de sortie étant conçue pour être d'une longueur sensi-

55

blement identique à la largeur d'une lame porte-objet de microscope ;

des moyens destinés à relier de façon amovible ledit élément de corps creux à une tête à embout dans ledit appareil et à établir un accès à ladite cavité intérieure pour un gaz ou un liquide fourni à travers ladite tête à embout.

32. Embout selon la revendication 31, dans lequel lesdits moyens de liaison amovible comprennent un tube creux communiquant avec ladite cavité intérieure et conçus pour être raccordés par ajustement serré à ladite tête à embout.




FIG. 1




FIG. 2




FIG. 3




FIG. 4A




FIG. 4B




FIG. 4C




FIG. 5C




FIG. 5B




FIG. 5A




FIG. 6A

FIG. 6B



FIG. 6C




FIG. 7A




FIG. 7B




FIG. 7C




FIG. 8A




FIG. 8B

FIG. 8C




FIG. 8E




FIG. 8D

FIG. 8F




FIG. 9A




FIG. 9B




FIG. 10




FIG. II B




FIG. II A




FIG. 12

**This Page is Inserted by IFW Indexing and Scanning
Operations and is not part of the Official Record**

BEST AVAILABLE IMAGES

Defective images within this document are accurate representations of the original documents submitted by the applicant.

Defects in the images include but are not limited to the items checked:

BLACK BORDERS

IMAGE CUT OFF AT TOP, BOTTOM OR SIDES

FADED TEXT OR DRAWING

BLURRED OR ILLEGIBLE TEXT OR DRAWING

SKEWED/SLANTED IMAGES

COLOR OR BLACK AND WHITE PHOTOGRAPHS

GRAY SCALE DOCUMENTS

LINES OR MARKS ON ORIGINAL DOCUMENT

REFERENCE(S) OR EXHIBIT(S) SUBMITTED ARE POOR QUALITY

OTHER: _____

IMAGES ARE BEST AVAILABLE COPY.

As rescanning these documents will not correct the image problems checked, please do not report these problems to the IFW Image Problem Mailbox.